

MURPHY WINDOW - BID REVIEW

MW Bid Platform Test Project | TEST-4320 | Rogers, MN

Base  
Generated 2026-08-21T18:40:39.090990+00:00  
Bid version B0.0.0

Configuration cfg-2026-08-19-v5 v5

Commercial Summary

| Direct Cost | Markup     | Selling Value | Margin | Total ft2 | \$/ft2 | Tax      | Contingency | Bond   |
|-------------|------------|---------------|--------|-----------|--------|----------|-------------|--------|
| \$18,092.72 | \$1,884.02 | \$19,976.74   | 9.43%  |           | 133.00 | \$150.20 | \$0.00      | \$0.00 |

Effective Pricing Configuration

| Configuration          | Base Product | Installation Material | Labor  | Tax Rate | Tax Status | Contingency | Bond | Wage | Precision                                                                                                                                                                                                                          |
|------------------------|--------------|-----------------------|--------|----------|------------|-------------|------|------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| cfg-2026-08-19-v5 / v5 | 10.00%       | 10.00%                | 15.00% | 0.00%    |            |             | No   | No   | Non-PW<br>{ "currency": "2", "currency_per_unit": "2", "dimension": "2", "labor_hours": "2", "linear_footage": "2", "multiplier": "2", "percentage": "2", "percentile": "2", "quantity": "2", "rate": "2", "square_footage": "2" } |

Cost Code Summary

| Code     | Description                               | Direct Cost | Markup % | Markup \$  | Selling Value | ft2    | \$/ft2   |
|----------|-------------------------------------------|-------------|----------|------------|---------------|--------|----------|
| 08 40 00 | Entrances, Storefronts, and Curtain Walls | \$16,142.72 | 10.46%   | \$1,689.02 | \$17,831.74   | 133.00 | \$134.07 |
| 07 90 00 | Joint Sealants                            | \$0.00      |          | \$0.00     | \$0.00        | 0.00   | \$0.00   |
| 14 40 00 | Lifts                                     | \$1,950.00  | 10.00%   | \$195.00   | \$2,145.00    | 0.00   | \$0.00   |

Bid Source Lineage

| Code     | Actual Code | Category              | Description                               | Source                                    | Direct Cost | Markup % | Selling Value |
|----------|-------------|-----------------------|-------------------------------------------|-------------------------------------------|-------------|----------|---------------|
| 08 40 00 | 08 40 00    | installation_material | Bracing and Anchoring                     | frame_material:sec_test_main:mat_bracing  | \$144.00    | 10.00%   | \$158.40      |
| 08 40 00 | 08 40 00    | installation_material | Sheet Metal Membrane Air Barriers         | frame_material:sec_test_main:mat_membrane | \$96.00     | 10.00%   | \$105.60      |
| 08 40 00 | 08 40 00    | installation_material | Flashing and Sheet Metal                  | frame_material:sec_test_main:mat_flashing | \$256.00    | 10.00%   | \$281.60      |
| 08 40 00 | 08 40 00    | installation_material | Backer Rods                               | frame_material:sec_test_main:mat_backer   | \$144.00    | 10.00%   | \$158.40      |
| 08 40 00 | 08 40 00    | installation_material | Joint Sealants                            | frame_material:sec_test_main:mat_sealant  | \$276.48    | 10.00%   | \$304.13      |
| 08 40 00 | 08 40 00    | installation_material | Tie Back                                  | frame_material:sec_test_main:mat_tieback  | \$90.00     | 10.00%   | \$99.00       |
| 08 40 00 | 08 40 00    | installation_material | Backpans / Insulation                     | frame_material:sec_test_main:mat_backpan  | \$579.84    | 10.00%   | \$637.82      |
| 08 40 00 | 08 40 00    | base_product          | Entrances, Storefronts, and Curtain Walls | quote:quo_test_a                          | \$12,875.00 | 10.00%   | \$14,162.50   |
| 14 40 00 | 14 40 00    | equipment             | 45' Boom Lift                             | equipment:eqp_test_lift                   | \$1,950.00  | 10.00%   | \$2,145.00    |
| 08 40 00 | 08 40 00    | field_labor           | Field installation                        | labor:lab_test_field                      | \$1,370.60  | 15.00%   | \$1,576.19    |
| 08 40 00 | 08 40 00    | shop_labor            | Shop preparation                          | labor:lab_test_shop                       | \$310.80    | 12.00%   | \$348.10      |

Scope and Cost Codes

| Code     | Description                               | Actual / MWD Code | MWD Description    | Deduct | Status |
|----------|-------------------------------------------|-------------------|--------------------|--------|--------|
| 08 40 00 | Entrances, Storefronts, and Curtain Walls | 0840              | Aluminum Entrances | No     | active |
| 07 90 00 | Joint Sealants                            | 0790              | Sealants           | No     | active |
| 14 40 00 | Lifts                                     |                   |                    | No     | active |

Quotes

| Code     | Vendor          | Date       | Price       | ft2    | Credit | Surcharge | Tax Included | Used | Notes                           |
|----------|-----------------|------------|-------------|--------|--------|-----------|--------------|------|---------------------------------|
| 08 40 00 | Example Glass A | 2026-08-17 | \$12,500.00 | 128.00 |        |           |              | Yes  | Yes<br>Selected training quote  |
| 08 40 00 | Example Glass B | 2026-08-17 | \$13,200.00 | 128.00 |        |           |              | No   | No<br>Comparison training quote |

Frame Takeoff

| Code     | Mark   | Qty  | Width | Height | ft2   | Perim. | Passes | Caulk LF | Head     | Sill     | Jamb | Type     | Material   | Finish   | Notes                        |
|----------|--------|------|-------|--------|-------|--------|--------|----------|----------|----------|------|----------|------------|----------|------------------------------|
| 08 40 00 | F-0001 | 2.00 | 48.00 | 96.00  | 64.00 | 48.00  | 3.00   | 144.00   | Standard | Standard |      | Standard | Storefront | Aluminum | Clear anodized<br>Main entry |
| 08 40 00 | F-0002 | 2.00 | 48.00 | 96.00  | 64.00 | 48.00  | 3.00   | 144.00   | Standard | Standard |      | Standard | Storefront | Aluminum | Clear anodized<br>Main entry |

Frame Installation Materials

| Code     | Material                          | Basis         | Operator | Factor | Quantity | Unit        | Unit Rate | Extended Cost | Override |
|----------|-----------------------------------|---------------|----------|--------|----------|-------------|-----------|---------------|----------|
| 08 40 00 | Bracing and Anchoring             | perimeter_lf  | multiply | 1.00   | 96.00    | linear foot | \$1.50    | \$144.00      | No       |
| 08 40 00 | Sheet Metal Membrane Air Barriers | perimeter_lf  | multiply | 1.00   | 96.00    | linear foot | \$1.00    | \$96.00       | No       |
| 08 40 00 | Flashing and Sheet Metal          | head_sill_qty | multiply | 1.00   | 32.00    | linear foot | \$8.00    | \$256.00      | No       |
| 08 40 00 | Backer Rods                       | caulking_lf   | multiply | 1.00   | 288.00   | linear foot | \$0.50    | \$144.00      | No       |
| 08 40 00 | Joint Sealants                    | caulking_lf   | multiply | 0.08   | 23.04    | sausage     | \$12.00   | \$276.48      | No       |
| 08 40 00 | Tie Back                          | tie_back_qty  | multiply | 1.00   | 2.00     | each        | \$45.00   | \$90.00       | No       |
| 08 40 00 | Backpans / Insulation             | backpan_lf    | multiply | 1.00   | 12.00    | linear foot | \$48.32   | \$579.84      | No       |

Equipment

| Code     | Description   | Quantity | Duration | Duration Unit | Rate  | Delivery | Notes                                                                                   |
|----------|---------------|----------|----------|---------------|-------|----------|-----------------------------------------------------------------------------------------|
| 14 40 00 | 45' Boom Lift | 1        |          | 1             | month | 1750     | 200<br>Owner-provided rental reference; verify stale vendor rate before commercial use. |

Borrowed Lites

| Code     | Mark | Description | Quantity | Width Inches | Height Inches | Rate | Notes                      |
|----------|------|-------------|----------|--------------|---------------|------|----------------------------|
| 08 40 00 | BL1  |             | 1        | 12           | 12            | 25   | Exercises five ft² minimum |

Labor

| Code     | Labor Type | Description        | Man Hours | Crew Size | Rate Override | Override Reason | Notes                                 |
|----------|------------|--------------------|-----------|-----------|---------------|-----------------|---------------------------------------|
| 08 40 00 | Field      | Field installation |           |           |               |                 | Owner-provided 2025 non-PW field rate |
| 08 40 00 | Shop       | Shop preparation   |           |           |               |                 | Owner-provided 2025 shop rate         |
| 14 40 00 | Field      |                    |           |           |               |                 |                                       |